

Hanes Excavation & Landscaping LLC

2977 Randall Rd
Ransomville, NY 14131-9618 US
7164256576
hanesexcavation@gmail.com

Estimate

ADDRESS

TOWN OF PENDLETON
CAMPBELL BLVD
PENDLETON, NY

SHIP TO

TOWN OF PENDLETON
CAMPBELL BLVD
PENDLETON, NY

ESTIMATE # 1308

DATE 11/12/2024

DESCRIPTION	QTY	RATE	AMOUNT
-------------	-----	------	--------

CONCRETE FLAT WORK:	1	19,650.00	19,650.00
---------------------	---	-----------	-----------

-POUR 5 PADS ON THE EAST SIDE OF THE BUILDING, 4 AT EACH EGRESS DOORS 5'X8'8"X4" AND ONE UNDER COVERED ROOF 32'X20'X6"
 -6" COMPACTED STONE BASE WITH 2" CRUSHER RUN UNDER EACH PAD.
 -USE EXPANSION JOINTS BETWEEN PADS AND BUILDING, THEN USE JOINT SEALER OVER EXPANSION JOINTS
 -USE WIRE MESH IN THE 4 SMALLER PADS AND #4 REBAR IN LARGE PAD 12" ON CENTER
 -ALL CONCRETE TO BE BROOM FINISH WITH SAW CUT JOINTS
 -DUE TO COLD WEATHER CONCRETE WOULD NOT BE SEALED AS IT WOULD NOT BE WARM ENOUGH SO THAT IS NOT INCLUDED.

Contact Hanes Excavation & Landscaping LLC to pay.	SUBTOTAL	19,650.00
ACCEPTANCE OF PROPOSAL- The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Half down is due at the start of the job and the rest of payment due upon completion of work. If remaining balance isn't paid within 30 days late fees are charged and interest is applied.	TAX	0.00
	TOTAL	\$19,650.00

* All work to be completed in a worklike manner according to standard practices. Any alteration or deviation from the above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge, over and above the estimate. All agreements are contingent upon weather, scheduling

and delays beyond our control. we are not responsible for any lawn, shrubs/trees or driveway damage incurred during normal operations. we are fully insured for your protection.

Accepted By

Accepted Date