

Payment Terms: Net 30			Project Name and Address
-			
Quote Date	Quote Number	Estimate Total	
4/17/2025	6030	\$23,976.00	Mason's Mission Park

## Description

Provide, deliver, and install 1,068 sq ft of TPV Pour-N-Place 50% Black 50% Blue with aromatic binder at a 8ft with 3.75" thickness.

Tear out of 1,068 sq ft as well as install 1,068 sq ft of stone. Town to provide the stone.

QTY	DESCRIPTION	SQ FT PRICE	TOTAL:
1,068 SQ FT	PIP Installation	\$17.08	\$18,238.00
1,068 SQ FT	Tear Out	\$2.00	\$2,136.00
1,068 SQ FT	Stone Instllation	\$1.50	\$1,602.00
Other	Freight	N/A	\$2,000.00



## Installation Inclusions:

Scope of work described in estimate only

Installation of any poured safety surface should occur at a minimum of 40 degrees F and rising. Installation should not occur during any percipitation. Play Surface Specialties will not be liable for any delays to schedule when project conditions do not meet those specified above.

Installation Exclusions: Permits/ Licensing, Fall Height Testing, Security/Fencing, Excavation and Site Work/
Preparation, Drainage, Stone, Extended Warranties

Due to the current condition of the transportation and polyurethane markets, quotes are only valid for 30 days